



NORTH EASTERN ELECTRIC POWER CORPORATION LIMITED

(A GOVERNMENT OF INDIA ENTERPRISE)

website: www.neepco.gov.in, E-mail: contract_neepco@yahoo.com

CONTRACTS & PROCUREMENT

ISO: 9001, 14001,
& OHSAS: 18001

BROOKLAND COMPOUND:: LOWER NEW COLONY

SHILLONG-793 003, MEGHALAYA, INDIA

Ph: 91-364-2226582 :: Fax: 91-364-2322578

Corrigendum No-1

To

NIB No.79 Dated 26.07.2013

FOR

**CONSTRUCTION OF BOUNDARY WALL AT PROPOSED NEEPCO TOWNSHIP,
MAWDIANGDIANG, SHILLONG(PHASE-1).**

The Bill of Quantity, Section-C, Volume-2 of Bid Documents of the above mentioned work has been revised which is enclosed as Revised BOQ.

For detail prospective bidders are requested to visit NEEPCO Website <http://www.neepco.gov.in>, or CPP's portal <http://www.eprocure.gov.in>.


Executive Director (C&P)

Revised Bill of Materials (As per Compendium 1 dated 21.8.13)

Construction of Boundary wall at proposed NEEPCO Township, Mawdiangdiang, Shillong (Phase-I).

Sl. No.	Description of Items	Unit	Qty.	Rate in figure(₹)	Rate in words(₹)	Amount in figure(₹)
1	Jungle cleaning including cutting bamboo and trees below 500 mm girth and removing the same outside the limit as directed. (b) Medium jungle.	Sqm	2380.00			
2	Earthwork in excavation in foundation trenches, including dressing of sides and ramming of the bottom including stacking serviceable stones, disposal and removal of excavated earth within a lead of 50 m and lift of 1.50 m complete as directed.					
	(c) Loose boulder above one man size or soil mixed with boulders above one man size or soft shale.	Cum	1201.34			
3	Providing 100 mm thick bedding with approved quality of stones including carriage, ramming, consolidating and filling the interstices with stone aggregates complete.	Sqm	527.94			
4	Providing & laying cement conc. in prop. 1:3:6 corresponding to M100 (1Cement, 3-sand, 6-stone aggregates of 40mm down graded) including necessary curing complete excluding shuttering. (b) Cement procured by contractor.	Cum	129.26			
5	Providing shuttering including centering for flat surface such as slabs, shelves, chajja and for vertical faces such as columns, walls, ends of beams etc with dressed plank not less than 25cm thick firmly fixed etc complete as directed (applicable upto 3.30 m height)	Sqm	2922.17			
6	(a) Providing for steel reinforcement in RCC work including cutting, bending, cranking and tying in position with binding wire, 20 gauge, as shown in drawings, complete upto floor two level. (i) Steel procured by contractor.	Qtl.	587.74			

Revised Bill of Quantities (As per Corrigendum 1 dated 21.8.13)

Construction of Boundary wall at proposed NEPCO Township, Mawdangdang, Shillong (Phase-I).						
Sl. No.	Description of Items	Unit	Qty.	Rate in figure(₹)	Rate in words(₹)	Amount in figure(₹)
7	Providing & laying cement conc. in prop. 1:1½:3 corresponding to M200 (1 Cement, 1½ sand, 3 stone aggregates of 20mm down graded) including necessary curing complete excluding shuttering and reinforcement. (a) Cement procured by contractor.	Cum	290.03			
8	Providing coursed random rubble stone masonry in foundation and plinth with unsized stone (mawthup) bonded with cement mortar of proportion 1:6 including curing complete. (Average size is not less than 20 cm x 20 cm x 25 cm) (a) Cement procured by contractor	Cum	631.29			
9	Providing 1 st class brick work in required thickness in cement mortar 1:6 (1-cement and 6-sand) including curing complete as directed.					
	(b) For walling (superstructure)					
	(c) Thickness 12.50 cm.					
	(a) cement procured by contractor.	Sqm	662.81			
10	Providing 12mm thick cement plaster including cleaning the surface and curing complete as directed (b) Proportion 1:3 (i) Cement procured by contractor	Sqm	1184.8			
11	Providing cement pointing in proportion 1:2 (1-cement: 2-sand) on stone work or brick work including curing complete as directed. (i) Cement procured by contractor	Sqm	2019.15			
12	Providing rough cast plaster in proportion of 1:3 (1-cement: 3-sand) over an under layer of 12 mm thick cement plaster of proportion 1:3 (1-cement: 3-sand) including curing complete as directed. (i) Cement procured by contractor	Sqm	3485.45			

Revised Bill of Quantities (As per Corrigendum 1 dated 21.8.13)

Construction of Boundary wall at proposed NEPCO Township, Mawdiangdiang, Shillong (Phase-I).						
Sl. No.	Description of Items	Unit	Qty.	Rate in figure(₹)	Rate in words(₹)	Amount in figure(₹)
13	Providing MS ornamental grills of approved design, joints continuously welded, with MS flat iron and bars for windows and railing etc. fitted and fixed with necessary screws or lugs complete with priming coat of red lead paint. (In ground floor)					
	(d) Grill weighing above 12 kg/m ² to 14 kg/m ² .	Sqm	714.00			
	(e) Grill weighing above 18 kg/m ² to 20 kg/m ² .	Sqm	15.00			
	(f) Extra for work in grill gate. (i) For hanging and locking arrangement including supply of materials and labour complete. @15% extra over the corresponding item of grill [i.e. item (e)].	Sqm	15.00			
14	Providing boulder or stone filling with boulders or stones 15 cm size, 60 cm wide behind the retaining wall etc. complete as directed.	Cum	100.22			
15	Painting with best quality synthetic enamel with approved make and brand including smoothening surface by sand papering etc. and using approved putty on the surface if necessary complete as directed.					
	(b) With commercial variety.					
	(iii) Two coats (new work)	Sqm	642.3			
			Total Amount			
	(Rupees.....)					